

SUBCONTRACT AGREEMENT

CIVIL AND EARTHWORKS PACKAGE

Contract reference: CW-2025-0417-CIV

Project: Northern Industrial Access Road and Platform, Package 4 — Civil Works

THIS AGREEMENT is made between AL-MURJAN INFRASTRUCTURE CONTRACTING COMPANY ("the Contractor") and RIDGEWAY CIVIL ENGINEERING LLC ("the Subcontractor") for the execution of the civil and earthworks described in the Bill of Quantities annexed hereto as Schedule 1.

The Subcontract Sum shall be ascertained by measurement and valuation of work actually executed at the rates and prices in Schedule 1, as qualified by Schedules 2 to 5 and by the General Conditions below. No lump sum is agreed.

Commencement date	05 January 2025
Date for completion	27 September 2025
Currency of account	Saudi Riyals (SAR)
Retention	5 per cent of each valuation
Working week	Sunday to Thursday inclusive
Rest days	Friday and Saturday

CONTENTS

Part I	General Conditions	Clauses 1 to 24
Part II	Measurement and Valuation	Clauses 25 to 39
Part III	Payment, Retention and Records	Clauses 40 to 52
Schedule 1	Bill of Quantities	Series A to E
Schedule 2	Site Zone Factors	
Schedule 3	Ground Classification Factors	
Schedule 4	Uplifts, Rebates and Limitations	
Schedule 5	Records Required as a Condition of Payment	
Schedule 6	Daywork Rates	
Schedule 7	Provisional and Prime Cost Sums	
Schedule 8	Preliminaries and General Items	
Part VI	Health, Safety and Environment	Clauses H1 to H15
Part IV	Specification Preambles	Clauses S1 to S20
Part V	Particular Conditions	Clauses P1 to P25
Appendix A	Definitions	
Appendix B	Form of Payment Application	
Appendix C	Insurances and Notices	

PART I — GENERAL CONDITIONS

1. Definitions

Words and expressions defined in Appendix A shall bear those meanings throughout. Where a word is used in both the singular and the plural the meaning is unaffected.

2. Subcontract documents

This Agreement, the General Conditions, Schedules 1 to 5 and Appendix A together constitute the whole agreement between the parties. In the event of conflict, a Schedule prevails over the General Conditions, and a later-numbered Schedule prevails over an earlier one.

3. Scope of the Works

The Subcontractor shall execute the civil and earthworks described in Schedule 1 at the locations shown on the Contract Drawings, together with all work reasonably to be inferred as necessary for their completion.

4. The Site

The Site is divided into four zones for the purposes of measurement, described in Schedule 2. The zone applicable to an item of work is the zone in which the work is physically executed, irrespective of where materials are stored or plant is based.

5. Ground conditions

The ground is classified into five categories described in Schedule 3. Classification shall be determined by the Engineer from the trial pit records and confirmed in writing before the work is executed. A classification once confirmed shall not be revised retrospectively.

6. Programme

The Subcontractor shall submit a programme within fourteen days of the Commencement Date and shall update it monthly.

7. Working hours

Normal working hours are 06:00 to 18:00 on working days. Work executed between 18:00 and 06:00 is Night Work and attracts the uplift stated in Schedule 4 where, and only where, that Schedule marks the item as eligible.

8. Rest days

The rest days under this Subcontract are Friday and Saturday. Work executed on a rest day attracts the rest-day uplift stated in Schedule 4 where the item is marked as eligible. No item attracts both the night uplift and the rest-day uplift on the same measurement unless the Engineer has instructed the work in writing under Clause 9.

9. Instructed out-of-hours working

The Engineer may instruct work outside normal working hours. An instruction shall be in writing and shall state whether the night uplift, the rest-day uplift, or both are to apply.

10. Care of the Works

The Subcontractor shall take full responsibility for the care of the Works until the date of the Taking-Over Certificate.

11. Setting out

The Subcontractor shall set out the Works from the primary control stations. Setting out is measured under item E.52.010 by chainage band and only against a joint survey signed by both parties.

12. Materials and workmanship

All materials shall be new and of the qualities described. Materials not described shall be of a quality approved by the Engineer.

13. Testing

The Subcontractor shall carry out the tests described in the Specification. Where Schedule 5 makes a test certificate a condition of payment, no valuation shall include the item until the certificate has been delivered.

14. Defective work

The Engineer may instruct the removal and re-execution of defective work. Re-execution is at the Subcontractor's cost and shall not be measured again.

15. Variations

The Engineer may instruct variations. A varied item shall be valued at the rates in Schedule 1 where the character and conditions of the work are not substantially changed.

16. Provisional sums

Provisional sums shall be expended only on the written instruction of the Engineer and shall be omitted from the Subcontract Sum if not so instructed.

17. Dayworks

Work instructed to be executed on a daywork basis shall be recorded on daywork sheets signed daily by the Engineer's representative. Daywork sheets not signed on the day of the work shall not be admitted.

18. Plant and standing time

Standing time is not payable except (a) where the Works are suspended by reason of adverse weather, in which case item E.51.010 applies against the meteorological record, and (b) plant standing measured under item E.51.030 against the plant standing record, each as required by Schedule 5.

19. Traffic management

Traffic management is measured by the day under item E.51.020. Not more than one day of traffic management is measurable per work area per day, irrespective of the number of locations at which signals are deployed.

20. Health and safety

The Subcontractor shall comply with the Project Health and Safety Plan.

21. Insurance

The Subcontractor shall maintain the insurances described in Appendix A throughout the period of the Works.

22. Assignment and subletting

The Subcontractor shall not assign this Subcontract nor sublet any part of the Works without written consent.

23. Suspension

The Contractor may suspend the Works on seven days' notice.

24. Termination

Either party may terminate on the grounds stated in Appendix A.

PART II — MEASUREMENT AND VALUATION

25. Principle of measurement

The Works shall be measured net as executed in accordance with the Civil Engineering Standard Method of Measurement, as modified by these Clauses. Where a Clause of this Part conflicts with the Method of Measurement, this Part prevails.

26. Units of measurement

Each item in Schedule 1 states the unit in which it is measured. No item shall be measured in any other unit, and a quantity presented in a unit other than that stated shall be rejected in its entirety rather than converted.

27. Build-up of rates

The rates in Schedule 1 are base rates. The sum payable for a measured quantity is ascertained by applying to the base rate, in the following order and no other: first the site zone factor from Schedule 2; then the ground classification factor from Schedule 3; then the night uplift, if applicable; then the rest-day uplift, if applicable; then the cumulative quantity rebate from Schedule 4, if the threshold has been passed; and the resulting sum is then rounded.

28. Rounding

Rounding shall be applied once only, to the rate after the whole of the build-up described in Clause 27 has been completed, to the nearest halala, a half halala being rounded upward. Rates shall not be rounded at intermediate steps. The amount for a measured quantity is the quantity multiplied by the rounded rate; where Clause 30 divides a quantity at a rebate threshold, each part is multiplied by its own rounded rate and the amount is their sum.

29. Application of factors

A factor applies to an item only where Schedule 2 or Schedule 3 lists that item's series. An item whose series is not listed is measured at the base rate irrespective of the zone or ground classification in which it is executed.

30. Cumulative quantity rebates

Where Schedule 4 states a rebate threshold for an item, the rebate applies to that part of the quantity which exceeds the threshold when taken cumulatively across the whole of the Works to date, and not to the quantity below it. The cumulative count runs from the Commencement Date, is not reset by a valuation, and is taken in order of the date of execution; measurements executed on the same date are taken in order of application number and then line number.

31. Daily limitations

Where Schedule 4 states a daily limitation for an item, no more than that quantity is measurable for that item, per work area, per day. A quantity in excess of the limitation is not payable and shall not be carried forward to a subsequent day.

32. Mutually exclusive items

Where Schedule 4 states that an item is excluded by another, the excluded item is not measurable within the stated number of days following the measurement of the excluding item on the same work area.

33. Surveyed items

Items marked as surveyed in Schedule 1 are measured only against a joint survey sheet signed by both parties. The quantity measured shall be the quantity on the survey sheet exactly.

34. Provisional quantities

Quantities in Schedule 1 are estimates and do not limit the quantity that may be measured.

35. Work not measurable

Temporary works, dewatering below the classified water table, and the removal of the Subcontractor's own waste are deemed included in the rates and are not separately measurable.

36. Disputed measurement

Where the parties cannot agree a measurement, the Engineer's measurement shall be used for the purposes of interim valuation without prejudice.

37. Re-measurement

The Contractor may re-measure any item within ninety days of the valuation in which it was first included.

38. Currency

All rates are in SAR and all valuations shall be stated in SAR. Amounts are stated in Riyals and halalas.

39. Errors in the Bill

An arithmetical error in Schedule 1 shall be corrected and shall not vitiate the rate.

PART III — PAYMENT, RETENTION AND RECORDS

40. Interim valuations

The Subcontractor shall submit a payment application monthly. Each application shall state the period of the Works it covers, being the first and last day on which any measured item included in it was executed.

41. Period of an application

An application covers a period which has closed. No application shall be submitted before the last day of the period it states, and no item shall be included in an application whose stated period does not include the day on which the work was executed. An application shall be submitted within 21 days of the end of the period it covers.

42. Content of an application

Each application shall list every item measured, stating the item code, the date of execution, the Site zone, the ground classification where applicable, the quantity, the unit, the built-up rate applied and the resulting amount.

43. Arithmetic

The total of an application shall equal the sum of the amounts of the items listed in it. An application whose total does not so agree shall be returned unpaid.

44. Duplicate measurement

No item shall be measured twice. Where the same item, work area and date appears more than once in an application, or in more than one application, the later measurement shall be disallowed in full.

45. Retention

The Contractor shall retain 5 per cent of the value of each valuation. Retention is calculated on the total of the application and not on individual items, and is rounded down to the nearest halala.

46. Records as a condition of payment

Where Schedule 5 states that a record is required for an item, the item is not payable in any valuation until that record has been delivered to the Engineer. The absence of a required record is a breach of this Clause and not merely a want of corroboration.

47. Form of records

A record required by Schedule 5 shall identify the work area, the date, the item code and the quantity, and shall be signed by the Subcontractor's foreman and countersigned by the Engineer's representative.

48. Payment period

The Contractor shall pay a correctly submitted application within thirty days of its receipt.

49. Set-off

The Contractor may set off against any sum due amounts properly due to it under this Subcontract.

50. Final account

The final account shall be submitted within ninety days of the Taking-Over Certificate.

51. Release of retention

One half of the retention shall be released on the Taking-Over Certificate and the balance on the expiry of the Defects Liability Period.

52. Interest

Interest on a late payment shall accrue at one per cent per month.

PART IV — SPECIFICATION PREAMBLES

S1. Setting out and control

Primary control stations are as shown on drawing CW-4-SU-001. The Subcontractor shall verify the stations before commencing and shall report any discrepancy exceeding 5 mm in plan or 3 mm in level.

S2. Topsoil strip

Topsoil shall be stripped to the full depth of the organic horizon and stockpiled separately in the location shown. Stripping to a depth greater than that instructed shall not be measured.

S3. Excavation tolerances

Formation levels shall be within plus or minus 20 mm of the levels shown. Over-excavation shall be made good with imported granular fill at the Subcontractor's cost and shall not be measured under item A.14.010.

S4. Classification of excavated material

Material shall be classified at the point of excavation and recorded on the daily excavation record. A classification not recorded on the day of excavation shall be taken to be G2 Firm Sabkha.

S5. Disposal

Material classified as unsuitable shall be removed to a licensed tip. Tip tickets shall accompany the payment application in which the disposal is measured.

S6. Compaction

Granular fill shall be placed in layers not exceeding 225 mm loose depth and compacted to 95 per cent of the maximum dry density. One compaction test shall be carried out per 500 m² per layer.

S7. Concrete materials

Cement shall be sulphate-resisting Portland cement. Aggregate shall be from an approved source and shall be tested for chloride content monthly.

S8. Concrete placing

Concrete shall not be placed when the shade air temperature exceeds 38 degrees Celsius without the written approval of the Engineer. Approval for placing at night does not of itself constitute an instruction under Clause 9.

S9. Curing

All concrete shall be cured for not less than seven days by an approved method. Curing is deemed included in the rates.

S10. Formwork

Formwork shall be of a quality producing the finish described. Formwork to soffits shall not be struck before the concrete has attained seventy-five per cent of its characteristic strength.

S11. Reinforcement

Reinforcement shall be measured by the theoretical mass of the bar schedule. Laps not shown on the schedule and tying wire, spacers and chairs are deemed included and are not separately measurable.

S12. Drainage bedding

Pipes shall be bedded in Class B granular bedding unless otherwise shown. Bedding is deemed included in the pipe rates.

S13. Pressure testing

Pressure pipework shall be tested in accordance with the Specification and the certificate delivered before the pipework is included in a valuation.

S14. Manholes

Precast manhole rings shall be bedded on a mortar joint. The depth measured shall be from finished cover level to the invert of the outgoing pipe.

S15. Sub-base

Type 1 granular sub-base shall be laid and compacted in a single layer where the compacted thickness does not exceed 250 mm.

S16. Bituminous materials

Bituminous materials shall be laid at a temperature not less than 130 degrees Celsius and shall not be laid in standing water.

S17. Surface course tolerances

The finished surface shall be within plus or minus 6 mm of the design level when tested with a 3 m straight edge.

S18. Kerbs

Kerbs shall be bedded on a concrete foundation and haunched to the detail shown. The foundation and haunching are deemed included.

S19. Road marking

Thermoplastic material shall be applied to a clean dry surface. Marking applied to a surface course less than fourteen days old shall be re-applied at the Subcontractor's cost.

S20. Adverse weather

Work shall be suspended when rainfall exceeds 5 mm in any hour. A suspension shall be recorded on the meteorological record, and standby under item E.51.010 is measurable only for the hours so recorded.

PART V — PARTICULAR CONDITIONS

P1. Precedence of this Part

This Part amends the General Conditions. Where a provision of this Part conflicts with Parts I to III, this Part prevails.

P2. Project-specific working restrictions

No work shall be executed in Zone Z3 Wadi Crossing during a declared flood watch. Standby during a flood watch is measurable under item E.51.010 and not under item E.51.030.

P3. Access to the Escarpment platform

Zone Z4 Escarpment is served by a single-track haul road. The Subcontractor shall programme deliveries to avoid simultaneous movements and shall not claim standing time arising from failure to do so.

P4. Restrictions on night working

Night work in Zone Z1 Compound requires the written consent of the Contractor by reason of the proximity of occupied accommodation. Consent does not of itself entitle the Subcontractor to the night uplift, which is payable only on the items marked in Schedule 4.

P5. Existing services

The Subcontractor shall carry out a service scan before any excavation and shall record the result. Damage to a service shown on the record is at the Subcontractor's cost.

P6. Statutory undertakers

Attendance on a statutory undertaker is measured under item E.53.010 and is limited to two days per work area per day of attendance irrespective of the number of undertakers attending.

P7. Archaeological finds

Work shall cease immediately on the discovery of a find of archaeological interest and shall not resume without the written instruction of the Engineer.

P8. Dust suppression

Dust suppression is deemed included in the rates and is not separately measurable, save that water bowser standing time during a declared dust event is measurable under item E.51.030.

P9. Working in high temperatures

Work shall be suspended between 12:00 and 15:00 during the period from 15 June to 15 September in accordance with the applicable labour regulations. Such a suspension is not a ground for standby.

P10. Ramadan working

Working hours during Ramadan shall be as agreed in writing before the commencement of the month. An agreed variation of hours does not of itself make work Night Work.

P11. Concurrent uplifts

For the avoidance of doubt, where an item is marked in Schedule 4 as attracting both the night uplift and the rest-day uplift, and the work is executed at night on a rest day, both uplifts apply only where the Engineer has so instructed in writing under Clause 9. In the absence of such an instruction the rest-day uplift alone applies.

P12. Rebate thresholds on variation

A rebate threshold stated in Schedule 4 is not adjusted by reason of a variation to the quantity of the item.

P13. Measurement of trench depth

Trench depth shall be measured from the existing ground level at the centre line of the trench to the invert of the pipe, and shall determine which of items A.12.020, A.12.030 and A.12.040 applies. Where a single trench spans two depth bands each part shall be measured separately.

P14. Rock classification disputes

Where the Subcontractor disputes a ground classification it shall give notice before excavating. A dispute raised after excavation shall be determined on the trial pit record alone.

P15. Imported fill sources

Imported granular fill shall be obtained from an approved borrow pit. Fill from an unapproved source shall not be measured.

P16. Testing frequency

Where the frequency of testing stated in the Specification is exceeded at the Engineer's instruction, the additional tests shall be valued as a variation.

P17. Concrete rejected at the point of delivery

Concrete rejected at the point of delivery shall not be measured. The delivery ticket shall be endorsed by both parties.

P18. Reinforcement wastage

Wastage on reinforcement is deemed included. The quantity measured is the theoretical mass on the approved bar schedule (Clause 33).

P19. Drainage testing before backfill

No length of drainage shall be backfilled before the pressure test has been witnessed. Item A.14.020 is not measurable within two days of the measurement of item A.14.010 on the same work area (Schedule 4, Part 5).

P20. Surfacing in adverse weather

Surface course shall not be laid when the road surface temperature is below 10 degrees Celsius or during rainfall.

P21. Traffic management during surfacing

Traffic management for surfacing is deemed included in the surfacing rates. Item E.51.020 is not measurable for a work area on a day on which any of items D.41.020, D.41.030, D.41.050, D.43.010 or D.43.020 is measured for that work area.

P22. Records in electronic form

A record required by Schedule 5 may be delivered in electronic form provided it bears both signatures required by Clause 47.

P23. Consequences of a missing record

Where an item requiring a record under Schedule 5 has been included in a valuation without that record, the amount shall be deducted from the next valuation together with any retention released upon it.

P24. Valuation of items not in Schedule 1

Work for which no rate appears in Schedule 1 shall be valued at daywork rates in Schedule 6 unless a rate is agreed in writing before the work is executed.

P25. Notices

A notice under this Subcontract shall be in writing and delivered to the address stated in Appendix A.

PART VI — HEALTH, SAFETY AND ENVIRONMENT

H1. Health and safety management

The Subcontractor shall appoint a full-time safety officer for the duration of the Works and shall maintain a safety file available for inspection at all times.

H2. Method statements and risk assessments

No activity shall commence before an approved method statement and risk assessment have been accepted by the Engineer. Work executed without an accepted method statement shall not be measured.

H3. Permits to work

A permit to work is required for excavation exceeding 1.2 m in depth, for any work in a confined space, for hot work, and for work within 3 m of a live service.

H4. Excavation support

No person shall enter an excavation exceeding 1.2 m in depth unless the sides are supported or battered to a safe angle. Earthwork support is measured under items A.15.010 and A.15.020.

H5. Personal protective equipment

Safety helmet, safety footwear, high-visibility clothing and eye protection shall be worn at all times on the Site.

H6. Heat stress

The Subcontractor shall implement the heat stress management plan, including the midday break required by Clause P9 and the provision of shaded rest areas and drinking water.

H7. Lifting operations

All lifting operations shall be planned by an appointed person and supervised by a competent lift supervisor.

H8. Traffic and pedestrian segregation

Vehicle routes and pedestrian routes shall be physically segregated. A banksman shall be provided for every reversing movement.

H9. Accident reporting

Any accident shall be reported to the Contractor within one hour and in writing within twenty-four hours.

H10. Environmental management

The Subcontractor shall comply with the Project Environmental Management Plan and shall not discharge any substance to ground or watercourse.

H11. Waste

Waste shall be segregated and removed to a licensed facility. Waste transfer notes shall be retained for the duration of the Works and produced on request.

H12. Noise

Noise at the boundary of the occupied accommodation in Zone Z1 shall not exceed 55 dB(A) between 20:00 and 06:00.

H13. Protection of watercourses

Silt-laden water shall not be discharged to the wadi. Settlement facilities are deemed included in the rates.

H14. Fuel and chemical storage

Fuel and chemicals shall be stored within bunded areas of not less than 110 per cent of the stored volume.

H15. Suspension for safety

The Contractor may suspend any activity on safety grounds. Such a suspension is not a ground for standby under item E.51.010 or E.51.030.

SCHEDULE 1 — BILL OF QUANTITIES

The rates below are base rates and are subject to the build-up described in Clause 27. They are exclusive of Value Added Tax.

Series A — Site Clearance and Earthworks

Code	Description	Unit	Est. qty	Rate (SAR)
A.11.010	Site clearance, vegetation and topsoil strip	m2	3,360	3.85
A.11.020	Removal of existing hardstanding, broken out	m2	3,880	12.40
A.12.010	General excavation to reduce level	m3	2,350	21.50
A.12.020	Excavation in trench, depth not exceeding 2 m	m3	2,675	34.80
A.12.030	Excavation in trench, depth 2 m to 4 m	m3	575	47.60
A.13.010	Disposal of excavated material off site	m3	2,600	18.90
A.13.020	Retention of excavated material on site, stockpiled	m3	500	6.40
A.14.010	Imported granular fill, placed and compacted	m3	425	53.20
A.14.020	Backfilling to trenches with selected arisings	m3	750	22.40
A.11.030	Grubbing up tree roots, girth exceeding 600 mm	no.	52	148.00
A.12.040	Excavation in trench, depth exceeding 4 m	m3	900	69.20
A.12.050	Excavation for manholes and chambers	m3	1,225	52.40
A.12.060	Trimming of formation to level and gradient	m2	2,480	6.90
A.13.030	Double handling of stockpiled material	m3	825	9.80
A.14.030	Geotextile separation membrane, laid and lapped	m2	1,720	14.60
A.15.010	Earthwork support to trenches, depth to 2 m	m2	1,080	31.80
A.15.020	Earthwork support to trenches, depth exceeding 2 m	m2	1,600	49.50
A.16.010	Dewatering by wellpoint, per week in operation	week	74	1,480.00

Series B — Concrete Works

Code	Description	Unit	Est. qty	Rate (SAR)
B.21.010	Blinding concrete, C15/20, thickness 75 mm	m2	4,000	29.60
B.21.020	Reinforced concrete to foundations, C32/40	m3	400	415.00
B.21.030	Reinforced concrete to slabs, C32/40	m3	725	389.00
B.22.010	Formwork to vertical faces, basic finish	m2	520	74.50
B.22.020	Formwork to soffits, propped, height to 3.5 m	m2	1,040	91.80
B.23.010	High-yield reinforcement bar, cut, bent and fixed	tonne	46	4,120.00
B.24.010	Waterstop to construction joints, 230 mm	lm	990	67.40
B.21.040	Reinforced concrete to walls, C32/40	m3	1,050	448.00

Code	Description	Unit	Est. qty	Rate (SAR)
B.21.050	Mass concrete fill to voids, C20/25	m3	1,375	296.00
B.22.030	Formwork to edges and risers, height to 500 mm	lm	1,170	42.60
B.23.020	Mesh reinforcement, A393, laid and lapped	m2	1,440	38.40
B.25.010	Cast-in sockets and holding-down bolt assemblies	no.	172	219.00
B.26.010	Surface treatment, power float to slabs	m2	2,120	17.20
B.27.010	Movement joint, 20 mm, sealed both faces	lm	1,890	89.50

Series C — Drainage and Ducting

Code	Description	Unit	Est. qty	Rate (SAR)
C.31.010	uPVC drainage pipe, 225 mm, laid and jointed	lm	570	86.20
C.31.020	Ductile iron pipe, 400 mm, laid and jointed	lm	960	214.00
C.32.010	Precast manhole, 1200 mm diameter, depth to 3 m	no.	116	1,860.00
C.32.020	Gully pot and connection to carrier drain	no.	168	287.00
C.33.010	Ducting, 4-way 110 mm, bedded in sand	lm	1,170	59.10
C.31.030	uPVC drainage pipe, 150 mm, laid and jointed	lm	1,350	54.80
C.31.040	Concrete surround to pipe, Class A bedding	lm	1,740	73.10
C.32.030	Precast manhole, 1800 mm diameter, depth to 5 m	no.	220	3,120.00
C.32.040	Manhole cover and frame, Class D400, bedded	no.	272	423.00
C.34.010	Headwall to outfall, precast, bedded	no.	196	965.00
C.35.010	CCTV survey of completed drainage run	lm	1,770	9.40

Series D — Pavements

Code	Description	Unit	Est. qty	Rate (SAR)
D.41.010	Sub-base, Type 1 granular, 250 mm compacted	m2	1,400	41.80
D.41.020	Dense bitumen macadam binder course, 60 mm	m2	1,920	63.50
D.41.030	Stone mastic asphalt surface course, 40 mm	m2	2,440	89.40
D.42.010	Precast concrete kerb, bedded and haunched	lm	1,350	71.20
D.43.010	Road marking, thermoplastic, 100 mm line	lm	1,650	14.80
D.41.040	Capping layer, 300 mm compacted	m2	2,960	32.60
D.41.050	Bitumen tack coat between courses	m2	3,480	6.20
D.42.020	Precast concrete channel, bedded and haunched	lm	1,740	64.80
D.42.030	Edging to footway, flat top, bedded	lm	2,130	39.40
D.43.020	Road marking, thermoplastic, hatched area	m2	2,720	42.60
D.44.010	Road stud, reflective, bedded in resin	no.	260	31.80

Series E — Ancillary Items and Standing Time

Code	Description	Unit	Est. qty	Rate (SAR)
E.51.010	Wet weather standby, plant and operator	hour	612	246.00
E.51.020	Traffic management, two-way signals, per day	day	192	684.00
E.52.010	Joint survey and setting out, chainage band	no.	244	478.00
E.51.030	Standing time, tracked excavator and operator	hour	924	312.00
E.53.010	Attendance on statutory undertaker	day	213	389.00
E.54.010	Temporary haul road, maintained, per week	week	162	876.00

Rates are per unit stated. No item may be measured in a unit other than the one shown (Clause 26). Quantities are estimates and do not limit the quantity that may be measured (Clause 34); they are given for tendering purposes only and are not a measurement.

SCHEDULE 2 — SITE ZONE FACTORS AND WORK AREAS

The factors below apply to every item in Series A, B, C and D. They do not apply to Series E, which is measured at the base rate in every zone.

Zone	Description	Factor
Z1 Compound	Within 500 m of the site compound	1
Z2 North Spur	North spur, 500 m to 2 km from the compound	1.06
Z3 Wadi Crossing	Wadi crossing and approaches, restricted access	1.145
Z4 Escarpment	Escarpment platform, single-track haul only	1.28

The zone applicable is the zone in which the work is physically executed (Clause 4). The factor is applied first in the build-up (Clause 27).

Work areas

For Clauses 19, 31, 32, 44 and P6 the Site is divided into the work areas below. A work area may extend into more than one zone.

Work area	Extent
S-01 Platform North	Northern half of the industrial platform
S-02 Platform South	Southern half of the industrial platform
S-03 Access Road	Access road, chainage 0+000 to 6+400
S-04 Drainage Corridor	Carrier drain corridor and outfall
S-05 Compound Extension	Extension to the site compound

SCHEDULE 2A — INDEXED RATES

The items below are priced by reference to the Site Materials Index, base 100.00 at 5 January 2025 (Clause 29A). The rate stated in Schedule 1 for these items is a base rate and is not payable as it stands.

Code	Description	Base rate	Unit
C.31.010	uPVC drainage pipe, 225 mm, laid and jointed	86.20	lm
D.41.030	Stone mastic asphalt surface course, 40 mm	89.40	m2

Site Materials Index, as published:

Month	Index	Month	Index
2025-01	100.00	2026-01	109.60
2025-02	100.40	2026-02	110.20
2025-03	101.10	2026-03	109.80
2025-04	101.80	2026-04	111.50
2025-05	102.60	2026-05	112.30
2025-06	103.90	2026-06	113.10
2025-07	104.70	2026-07	112.40
2025-08	104.20	2026-08	113.80
2025-09	105.30	2026-09	114.60
2025-10	106.80	2026-10	115.20
2025-11	107.40	2026-11	115.90
2025-12	108.10	2026-12	116.50

SCHEDULE 2B — RATES IN UNITED STATES DOLLARS

The rate stated in Schedule 1 for the items below is in USD and is converted under Clause 26A at the rate published for the month in which the work was executed.

Code	Description	Rate (USD)	Unit
B.23.020	Mesh reinforcement, A393, laid and lapped	38.40	m2
B.25.010	Cast-in sockets and holding-down bolt assemblies	219.00	no.
C.32.040	Manhole cover and frame, Class D400, bedded	423.00	no.

Rate of exchange, as published:

Month	Halalas per USD	Month	Halalas per USD
2025-01	375.00	2026-01	376.00
2025-02	375.10	2026-02	375.80
2025-03	375.00	2026-03	375.90
2025-04	374.90	2026-04	376.20
2025-05	375.20	2026-05	376.40
2025-06	375.30	2026-06	376.10
2025-07	375.10	2026-07	375.70
2025-08	375.00	2026-08	376.30
2025-09	374.80	2026-09	376.60
2025-10	375.40	2026-10	376.80
2025-11	375.60	2026-11	377.00
2025-12	375.50	2026-12	376.50

SCHEDULE 3 — GROUND CLASSIFICATION FACTORS

The factors below apply only to the items listed beneath the table. An item not listed is measured without regard to the ground classification (Clause 29).

Class	Description	Factor
G1 Loose Sand	Loose windblown sand, no excavation support required	0.94
G2 Firm Sabkha	Firm sabkha, the datum classification	1
G3 Cemented Fill	Cemented fill and demolition arisings	1.12
G4 Weathered Rock	Weathered rock, rippable by tracked plant	1.375
G5 Sound Rock	Sound rock requiring breaking or hydraulic splitting	1.63

Items to which Schedule 3 applies

A.11.020, A.12.010, A.12.020, A.12.030, A.12.040, A.12.050, A.14.020, A.15.010, A.15.020, C.31.010, C.31.020, C.31.030, C.32.010, C.32.030, C.33.010.

G2 Firm Sabkha is the datum and carries a factor of 1. The ground factor is applied after the zone factor and before any uplift (Clause 27).

SCHEDULE 4 — UPLIFTS, REBATES AND LIMITATIONS

Part 1 — Night working uplift

The following items, and no others, attract an uplift where the work is executed between 18:00 and 06:00.

Code	Description	Uplift
A.12.020	Excavation in trench, depth not exceeding 2 m	18%
A.12.030	Excavation in trench, depth 2 m to 4 m	18%
A.14.010	Imported granular fill, placed and compacted	18%
B.21.020	Reinforced concrete to foundations, C32/40	22%
B.21.030	Reinforced concrete to slabs, C32/40	22%
C.31.010	uPVC drainage pipe, 225 mm, laid and jointed	18%
D.41.020	Dense bitumen macadam binder course, 60 mm	25%
D.41.030	Stone mastic asphalt surface course, 40 mm	25%
D.43.010	Road marking, thermoplastic, 100 mm line	25%
A.12.040	Excavation in trench, depth exceeding 4 m	18%
B.21.040	Reinforced concrete to walls, C32/40	22%
C.31.030	uPVC drainage pipe, 150 mm, laid and jointed	18%
D.43.020	Road marking, thermoplastic, hatched area	25%

Part 2 — Rest-day uplift

The following items attract an uplift where the work is executed on Friday and Saturday.

Code	Description	Uplift
B.21.020	Reinforced concrete to foundations, C32/40	35%
B.21.030	Reinforced concrete to slabs, C32/40	35%
D.41.030	Stone mastic asphalt surface course, 40 mm	35%
B.21.040	Reinforced concrete to walls, C32/40	35%

Part 3 — Banded quantities

Clause 30 is substituted. The quantity measured for an item in a Contract Year is taken in the bands below, each part of it at the percentage of the rate shown against its band. The bands are counted from zero at the start of each Contract Year (Clause 3A), and a measurement that crosses a band is divided at the band.

Code	Description	Band	Unit	Per cent of rate
A.12.010	General excavation to reduce level	1 to 4,000	m3	100%
A.12.010	General excavation to reduce level	4,001 to 16,000	m3	96%
A.12.010	General excavation to reduce level	above 16,000	m3	93%
A.12.020	Excavation in trench, depth not exceeding 2 m	1 to 1,500	m3	100%

Code	Description	Band	Unit	Per cent of rate
A.12.020	Excavation in trench, depth not exceeding 2 m	1,501 to 6,000	m3	97%
A.12.020	Excavation in trench, depth not exceeding 2 m	above 6,000	m3	94%
A.13.010	Disposal of excavated material off site	1 to 5,000	m3	100%
A.13.010	Disposal of excavated material off site	5,001 to 20,000	m3	94%
A.13.010	Disposal of excavated material off site	above 20,000	m3	90%
A.14.010	Imported granular fill, placed and compacted	1 to 2,000	m3	100%
A.14.010	Imported granular fill, placed and compacted	2,001 to 8,000	m3	95%
A.14.010	Imported granular fill, placed and compacted	above 8,000	m3	91%
B.22.010	Formwork to vertical faces, basic finish	1 to 1,200	m2	100%
B.22.010	Formwork to vertical faces, basic finish	1,201 to 4,800	m2	96%
B.22.010	Formwork to vertical faces, basic finish	above 4,800	m2	93%
B.23.010	High-yield reinforcement bar, cut, bent and fixed	1 to 60	tonne	100%
B.23.010	High-yield reinforcement bar, cut, bent and fixed	61 to 240	tonne	97%
B.23.010	High-yield reinforcement bar, cut, bent and fixed	above 240	tonne	94%
D.41.010	Sub-base, Type 1 granular, 250 mm compacted	1 to 4,500	m2	100%
D.41.010	Sub-base, Type 1 granular, 250 mm compacted	4,501 to 18,000	m2	95%
D.41.010	Sub-base, Type 1 granular, 250 mm compacted	above 18,000	m2	92%
D.41.040	Capping layer, 300 mm compacted	1 to 3,500	m2	100%
D.41.040	Capping layer, 300 mm compacted	3,501 to 14,500	m2	95%
D.41.040	Capping layer, 300 mm compacted	above 14,500	m2	92%

Part 4 — Daily limitations

Not more than the quantity below is measurable for the item, per work area, per day (Clause 31).

Code	Description	Limit	Unit
A.11.010	Site clearance, vegetation and topsoil strip	4,500	m2
A.12.010	General excavation to reduce level	1,200	m3
B.21.020	Reinforced concrete to foundations, C32/40	140	m3
C.32.010	Precast manhole, 1200 mm diameter, depth to 3 m	6	no.
D.41.030	Stone mastic asphalt surface course, 40 mm	3,200	m2
E.51.020	Traffic management, two-way signals, per day	1	day
A.13.030	Double handling of stockpiled material	800	m3
C.32.030	Precast manhole, 1800 mm diameter, depth to 5 m	3	no.
E.53.010	Attendance on statutory undertaker	2	day

Part 5 — Mutually exclusive items

The item in the first column is not measurable within the stated period following measurement of the item in the second column on the same work area (Clause 32).

Excluded item	Excluded by	Period
A.14.020	A.14.010	2 days

Part 6 — Surveyed items

The following items are measured only against a joint survey sheet signed by both parties (Clause 33).

Code	Description	Unit
B.23.010	High-yield reinforcement bar, cut, bent and fixed	tonne
E.52.010	Joint survey and setting out, chainage band	no.
B.23.020	Mesh reinforcement, A393, laid and lapped	m2

Nothing in this Schedule permits both the night uplift and the rest-day uplift to be applied to the same measurement save on the written instruction of the Engineer (Clause 8).

SCHEDULE 5 — RECORDS REQUIRED AS A CONDITION OF PAYMENT

The items listed below are not payable in any valuation until the record named against them has been delivered to the Engineer. Each record bears a reference from the series shown, and that reference is quoted against the line in the Application (Clause 47A). The record is written in the words of the person who did the work and does not repeat the description in Schedule 1.

Code	Description	Record required	Reference series
A.12.030	Excavation in trench, depth 2 m to 4 m	Daily Excavation Record	DX
A.14.010	Imported granular fill, placed and compacted	Compaction Test Certificate	CT
B.21.020	Reinforced concrete to foundations, C32/40	Concrete Pour Record	PR
B.21.030	Reinforced concrete to slabs, C32/40	Concrete Pour Record	PR
C.31.020	Ductile iron pipe, 400 mm, laid and jointed	Pressure Test Certificate	PT
D.41.010	Sub-base, Type 1 granular, 250 mm compacted	Compaction Test Certificate	CT
E.51.010	Wet weather standby, plant and operator	Meteorological Record	MO
A.12.040	Excavation in trench, depth exceeding 4 m	Daily Excavation Record	DX
A.16.010	Dewatering by wellpoint, per week in operation	Dewatering Log	DW
B.21.040	Reinforced concrete to walls, C32/40	Concrete Pour Record	PR
C.32.030	Precast manhole, 1800 mm diameter, depth to 5 m	Pressure Test Certificate	PT
C.35.010	CCTV survey of completed drainage run	CCTV Survey Report	CV
D.41.040	Capping layer, 300 mm compacted	Compaction Test Certificate	CT
E.51.030	Standing time, tracked excavator and operator	Plant Standing Record	PS
B.23.010	High-yield reinforcement bar, cut, bent and fixed	Joint Survey Sheet	JS
E.52.010	Joint survey and setting out, chainage band	Joint Survey Sheet	JS
B.23.020	Mesh reinforcement, A393, laid and lapped	Joint Survey Sheet	JS

A record covering a week records each day worked. A week is measurable only where the record shows work on not fewer than five days of that week (Clause 47A).

SCHEDULE 6 — DAYWORK RATES

The rates below apply only to work instructed to be executed on a daywork basis under Clause 17, and to work for which no rate appears in Schedule 1 (Clause P24). Daywork sheets shall be signed on the day of the work.

Part 1 — Labour

Grade	Unit	Rate (SAR)
Ganger	hour	78.50
Skilled operative	hour	64.20
Semi-skilled operative	hour	51.80
General operative	hour	43.60
Banksman	hour	46.90
Steel fixer	hour	71.40
Carpenter, formwork	hour	73.10
Pipelayer	hour	66.30
Site engineer	hour	118.00
Foreman	hour	96.50

Part 2 — Plant

Plant	Unit	Rate (SAR)
Tracked excavator, 21 tonne, with operator	hour	246.00
Tracked excavator, 13 tonne, with operator	hour	188.00
Wheeled loader, 12 tonne, with operator	hour	174.00
Articulated dump truck, 25 tonne, with operator	hour	212.00
Tipper lorry, 8 wheel, with driver	hour	156.00
Vibrating roller, 12 tonne, with operator	hour	138.00
Plate compactor	hour	34.00
Concrete pump, boom, with operator	hour	398.00
Mobile crane, 50 tonne, with operator	hour	472.00
Dewatering pump, 100 mm, with hoses	week	1,240.00
Wellpoint system, 30 m run	week	3,860.00
Site dumper, 6 tonne, with operator	hour	98.00

Part 3 — Percentage additions

Category	Addition
Labour, to cover supervision and overheads	68%
Plant, to cover fuel, maintenance and overheads	22%

Category	Addition
Materials, to cover handling and overheads	14%
Subcontracted daywork	10%

The percentage additions are applied to the net cost and are the only additions allowable. No profit is added separately.

SCHEDULE 7 — PROVISIONAL AND PRIME COST SUMS

The sums below are included in the Subcontract Sum and shall be expended only on the written instruction of the Engineer (Clause 16). A sum not so instructed shall be omitted.

Reference	Description	Sum (SAR)
PS.01	Diversion of 11 kV overhead line by the utility	420,000.00
PS.02	Ground investigation, additional boreholes	185,000.00
PS.03	Archaeological watching brief	96,000.00
PS.04	Landscaping to the northern boundary	310,000.00
PS.05	Street lighting columns and connections	268,000.00
PC.01	Precast concrete headwalls, supply only	142,000.00
PC.02	Manhole covers and frames, supply only	88,500.00
PC.03	Drainage pipework, supply only	515,000.00

A provisional sum (PS) covers work not yet defined. A prime cost sum (PC) covers materials to be supplied by others. Neither is measured under Schedule 1.

SCHEDULE 8 — PRELIMINARIES AND GENERAL ITEMS

The items below are measured as stated. An item priced against the unit "item" is a fixed charge and is valued once, in the valuation in which the obligation is discharged. An item priced by the week is a time-related charge and is valued for each week in which the Works are in progress.

Reference	Description	Unit	Amount (SAR)
PR.01	Site establishment, offices and welfare	item	486,000.00
PR.02	Site accommodation, maintained, per week	week	14,200.00
PR.03	Temporary fencing and hoarding, erected	lm	218.00
PR.04	Site signage and safety notices	item	38,500.00
PR.05	Temporary power supply and distribution	item	164,000.00
PR.06	Temporary water supply	item	92,000.00
PR.07	Setting-out equipment and survey instruments	item	78,000.00
PR.08	Safety officer, full time	week	9,800.00
PR.09	First aid facilities and trained personnel	week	2,400.00
PR.10	Site cleaning and waste removal	week	6,700.00
PR.11	Progress photographs, monthly	month	1,900.00
PR.12	As-built records and O&M manuals	item	142,000.00
PR.13	Testing and commissioning attendance	item	88,000.00
PR.14	Demobilisation and reinstatement of the compound	item	214,000.00

Preliminaries are not subject to the zone factor, the ground factor, or any uplift or rebate. They are valued at the amounts stated (Clause 29).

Valuation of time-related preliminaries

A week in which the Works are suspended under Clause 23 or Clause H15 is a week in which the Works are in progress for the purposes of this Schedule, save that no time-related preliminary is valued for a week in which no work whatever was executed on the Site.

PART VII — PARTICULAR CONDITIONS (SECOND SERIES)

3A. Contract Years

The first Contract Year runs from the Commencement Date to the day before its first anniversary. Each following Contract Year runs from that anniversary. The final Contract Year ends on the Date for Completion as extended by any Amendment, however long that leaves it; an extension of time does not begin a new Contract Year.

6A. Chargeable Hour

Where an item is measured by the hour, a Chargeable Hour is an hour of attendance other than the first hour of that attendance. The site record states the hours attended; the quantity measured is one hour fewer.

26A. Rates stated in another currency

Where Schedule 1 states a rate in USD, the rate is converted at the rate of exchange published in Schedule 2B for the calendar month in which the work was executed, and the converted figure is rounded to the nearest halala with a half rounded to the nearer even halala. The conversion is made before any factor or uplift is applied.

27A. Conditions on the uplifts and factors

The night-working uplift is not payable on an item priced at a zone factor exceeding 1.1, the allowance for working away from the compound being taken to include it. In any period of extension of time granted by an Amendment, that is to say for work executed after 27 September 2025, the ground classification is taken as G2 Firm Sabkha whatever the Engineer recorded on the day.

29A. Indexed rates

The rate for an item listed in Schedule 2A is the base rate stated in Schedule 1 multiplied by the Site Materials Index published for the calendar month in which the work was executed and divided by the base index, and rounded to the nearest halala with a half rounded to the nearer even halala. That figure is then treated as the rate for the purposes of Clause 27, and Clause 28 applies to the build-up as usual.

31A. Instruments taking effect before their date of issue

Where an Amendment substitutes a rate with effect from a date before the date on which it was issued, an Application for Payment submitted before that date of issue is not thereby incorrect: it was valued at the rate then in force. The difference between the rates on work already valued shall be shown as a single adjustment on the first Application for Payment submitted on or after the date of issue, and on no other.

33A. Tolerance on measurement

Where an item is measured against a joint survey, a measured quantity not exceeding the surveyed quantity by more than 2 per cent is payable as measured. A measured quantity exceeding the surveyed quantity by more than that is payable at the surveyed quantity only.

45A. Release of retention

On the first Application for Payment submitted after the Date for Completion as extended, one half of the retention held on all earlier Applications is released, rounded down to the halala. The amount payable on an Application is the measured total, plus any adjustment under Clause 31A, less the retention deducted on it, plus any retention released under this Clause.

47A. Site records and their references

A site record is written by the person who carried out the work and is not required to adopt the wording of the Bill of Quantities. Each record bears a reference from the series stated in Schedule 5 against the item it evidences, and that reference is quoted against the line in the Application. A record that evidences a week records each day worked; a week is measurable only where the record shows work on not fewer than five days of that week.

APPENDIX A — DEFINITIONS

Commencement Date	the date stated in the Agreement on which the Subcontractor is to begin the Works.
Contract Drawings	the drawings listed in the Specification and any revision issued by the Engineer.
Day	a calendar day, including a rest day.
Engineer	the person appointed by the Contractor to administer this Subcontract, or that person's representative.
Ground classification	the category assigned under Clause 5 and listed in Schedule 3.
Halala	one hundredth part of a Saudi Riyal.
Night Work	work executed between 18:00 and 06:00.
Period	in relation to a payment application, the span of days stated in it under Clause 40.
Rest day	Friday and Saturday.
Work area	each of the five parts of the Site listed in Schedule 2, being the unit to which Clauses 19, 31, 32, 44 and P6 apply.
Site	the land made available to the Subcontractor, divided into the zones described in Schedule 2.
Taking-Over Certificate	the certificate issued by the Engineer on completion of the Works.
Valuation	the ascertainment of the sum due in respect of a payment application.
Working day	a day other than a rest day.
Works	the whole of the work to be executed under this Subcontract.

EXECUTION

IN WITNESS WHEREOF the parties have executed this Subcontract on the date first written above.

For and on behalf of the Contractor _____

For and on behalf of the Subcontractor _____

This document comprises the pages numbered consecutively at the foot and no others.

APPENDIX B — FORM OF PAYMENT APPLICATION

Every application shall be in the form below. The example assumes no earlier quantity of any item has been measured.

Application number	PA-000xx
Period covered	from 06/05/2025 to 13/05/2025
Date of submission	22/05/2025
Work area	S-03 Access Road
Site zone	Z2 North Spur

Measured items

Item	Date	Zone	Ground	Qty	Unit	Rate	Amount
A.12.020	06/05/2025	Z2	G4	180	m3	50.72	9,129.60
A.14.020	07/05/2025	Z2	G2	96	m3	23.74	2,279.04
C.31.010	13/05/2025	Z2	G2	48	lm	91.37	4,385.76
Total of measured items							15,794.40
Less retention at 5 per cent							789.72
Net amount of this application							15,004.68

The total of the measured items shall equal the sum of the amounts listed (Clause 43). Retention is calculated on that total and rounded down to the halala (Clause 45).

APPENDIX C — INSURANCES AND NOTICES

Insurances to be maintained

Policy	Minimum indemnity	Period
Contractor's all risks	Full reinstatement value	To the Taking-Over Certificate
Public liability	10,000,000 SAR any one event	To the end of the Defects Liability Period
Employer's liability	5,000,000 SAR	Throughout
Motor and plant	2,000,000 SAR	Throughout
Professional indemnity	3,000,000 SAR	Six years from completion

Addresses for notices

The Contractor	Al-Murjan Infrastructure Contracting Company, Commercial District, Dammam
The Subcontractor	Ridgeway Civil Engineering LLC, Industrial Area 2, Jubail
The Engineer	Northern Access Road Project Office, Site Compound Z1

A notice sent to an address other than the one stated above is not validly given.

SCHEDULE OF VARIATIONS

The Subcontract is to be read with the instruments below, in the order issued. Each takes effect on its own effective date and governs work executed on or after it; nothing in an instrument reopens work already measured at the rate then payable.

Instrument	Issued	Effective	What it changes
Supplement No. 1	2025-03-24	2025-05-01	rates: B.23.010, B.21.020, A.16.010; monthly rate: D.41.020
Amendment No. 1	2025-08-18	2025-09-28	completion to 2026-03-31; rates: E.54.010, B.23.010
Supplement No. 2	2025-11-12	2025-12-01	rates: D.41.020; 5 per cent on C.32.030, C.32.010, D.41.020, B.23.010
Amendment No. 2	2026-02-16	2026-04-01	completion to 2026-09-30; monthly rate: E.54.010; 8 per cent on C.32.030, C.32.010, D.41.020, B.23.010
Amendment No. 3	2026-05-12	2025-11-01	rates: C.32.010, A.14.010

The Term as let ran from 5 January 2025 to 27 September 2025. As twice extended it runs from 5 January 2025 to 30 September 2026.

A rate stated in the Bill of Quantities is the rate payable only until an instrument substitutes another for it. Pricing a measured quantity therefore requires the date on which the work was executed, not the date of the payment application.

SUPPLEMENT NO. 1 TO SUBCONTRACT CW-2025-0417-CIV

Reference CW-2025-0417-CIV/S1. Issued 24 March 2025 and taking effect 1 May 2025.

Indexation of material-led rates under Clause 26.4, the parties having agreed that the reinforcement and concrete rates in the Bill of Quantities no longer reflect delivered cost.

1.1 Substituted rates

The rates below are substituted for the rates in the Bill of Quantities for work executed on or after the effective date stated against each. Work executed before that date is measured at the rate previously payable.

Item	Description	Unit	Rate previously payable	Rate payable	Effective
B.23.010	High-yield reinforcement bar, cut,	tonne	4,120.00	4,385.00	2025-05-01
B.21.020	Reinforced concrete to foundations	m3	415.00	431.50	2025-05-01
A.16.010	Dewatering by wellpoint, per week	week	1,480.00	1,524.00	2025-05-01

1.2 Monthly re-measurement, item D.41.020

Item D.41.020 (Dense bitumen macadam binder course, 60 mm) is re-published monthly against the Bitumen Index (Kingdom, per tonne). The rate payable for a measured quantity is the rate published for the calendar month in which the work was executed. Where work is executed in a month later than the last month stated below, the rate last published applies until it is superseded.

Month of execution	Rate payable
May 2025	214.50
June 2025	219.80
July 2025	226.40
August 2025	223.10
September 2025	220.50

Save as stated above, the Subcontract is unchanged and remains in full force. Where this instrument and an earlier instrument both state a rate or a discount for the same item, the later governs work executed on or after its effective date, and the earlier governs work executed before it.

AMENDMENT NO. 1 TO SUBCONTRACT CW-2025-0417-CIV

Reference CW-2025-0417-CIV/A1. Issued 18 August 2025 and taking effect 28 September 2025.

Extension of time under Clause 14.2 for the drainage corridor and the compound extension, together with the rates payable in the extended period.

1.1 Extension of time

The Date for Completion stated in the Form of Subcontract is extended to 31 March 2026 (extension of time, 185 days). The Date of Possession is unchanged. Work executed on or before the extended Date for Completion is measurable and payable under this Subcontract; work executed after it is not.

1.2 Substituted rates

The rates below are substituted for the rates in the Bill of Quantities for work executed on or after the effective date stated against each. Work executed before that date is measured at the rate previously payable.

Item	Description	Unit	Rate previously payable	Rate payable	Effective
E.54.010	Temporary haul road, maintained, p	week	876.00	948.00	2025-10-01
B.23.010	High-yield reinforcement bar, cut,	tonne	4,385.00	4,450.00	2025-10-01

Save as stated above, the Subcontract is unchanged and remains in full force. Where this instrument and an earlier instrument both state a rate or a discount for the same item, the later governs work executed on or after its effective date, and the earlier governs work executed before it.

SUPPLEMENT NO. 2 TO SUBCONTRACT CW-2025-0417-CIV

Reference CW-2025-0417-CIV/S2. Issued 12 November 2025 and taking effect 1 December 2025.

Volume discount on the principal measured items, the Employer having committed the second platform to this Subcontract.

2.1 Substituted rates

The rates below are substituted for the rates in the Bill of Quantities for work executed on or after the effective date stated against each. Work executed before that date is measured at the rate previously payable.

Item	Description	Unit	Rate previously payable	Rate payable	Effective
D.41.020	Dense bitumen macadam binder cours	m2	220.50	228.00	2025-12-01

2.2 Discount on principal items

A discount of 5 per cent is allowed on the items listed below for work executed on or after 1 December 2025. The discount is applied as the final factor in the build-up required by Clause 27, before the rounding required by Clause 28, and after any rebate under Clause 30. Work executed before that date carries no discount.

Item	Description
C.32.030	Precast manhole, 1800 mm diameter, depth to 5 m
C.32.010	Precast manhole, 1200 mm diameter, depth to 3 m
D.41.020	Dense bitumen macadam binder course, 60 mm
B.23.010	High-yield reinforcement bar, cut, bent and fixed

Save as stated above, the Subcontract is unchanged and remains in full force. Where this instrument and an earlier instrument both state a rate or a discount for the same item, the later governs work executed on or after its effective date, and the earlier governs work executed before it.

AMENDMENT NO. 2 TO SUBCONTRACT CW-2025-0417-CIV

Reference CW-2025-0417-CIV/A2. Issued 16 February 2026 and taking effect 1 April 2026.

Second extension of time, deepening of the Supplement No. 2 discount, and monthly indexation of the haul road rate.

2.1 Extension of time

The Date for Completion stated in the Form of Subcontract is extended to 30 September 2026 (second extension of time, 183 days). The Date of Possession is unchanged. Work executed on or before the extended Date for Completion is measurable and payable under this Subcontract; work executed after it is not.

2.2 Monthly re-measurement, item E.54.010

Item E.54.010 (Temporary haul road, maintained, per week) is re-published monthly against the Plant Hire Index (Eastern Province, per week). The rate payable for a measured quantity is the rate published for the calendar month in which the work was executed. Where work is executed in a month later than the last month stated below, the rate last published applies until it is superseded.

Month of execution	Rate payable
April 2026	976.00
May 2026	991.00
June 2026	1,013.00
July 2026	1,038.00
August 2026	1,038.00
September 2026	1,052.00

2.3 Discount on principal items

A discount of 8 per cent is allowed on the items listed below for work executed on or after 1 April 2026. The discount is applied as the final factor in the build-up required by Clause 27, before the rounding required by Clause 28, and after any rebate under Clause 30. Work executed before that date carries no discount.

Item	Description
C.32.030	Precast manhole, 1800 mm diameter, depth to 5 m
C.32.010	Precast manhole, 1200 mm diameter, depth to 3 m
D.41.020	Dense bitumen macadam binder course, 60 mm
B.23.010	High-yield reinforcement bar, cut, bent and fixed

Save as stated above, the Subcontract is unchanged and remains in full force. Where this instrument and an earlier instrument both state a rate or a discount for the same item, the later governs work executed on or after its effective date, and the earlier governs work executed before it.

AMENDMENT NO. 3 TO SUBCONTRACT CW-2025-0417-CIV

Reference CW-2025-0417-CIV/A3. Issued 12 May 2026 and taking effect 1 November 2025.

Settlement of the Subcontractor's claim under Clause 26.6. The rates below are substituted with effect from 1 November 2025, which is before the date of this Amendment. Work executed on or after that date and already certified shall be re-measured at the substituted rates, and the difference shown as a single adjustment on the first Application for Payment submitted after the date of issue (Clause 31A).

3.1 Substituted rates

The rates below are substituted for the rates in the Bill of Quantities for work executed on or after the effective date stated against each. Work executed before that date is measured at the rate previously payable.

Item	Description	Unit	Rate previously payable	Rate payable	Effective
C.32.010	Precast manhole, 1200 mm diameter,	no.	1,860.00	1,984.00	2025-11-01
A.14.010	Imported granular fill, placed and	m3	53.20	56.80	2025-11-01

Save as stated above, the Subcontract is unchanged and remains in full force. Where this instrument and an earlier instrument both state a rate or a discount for the same item, the later governs work executed on or after its effective date, and the earlier governs work executed before it.